सत्यमेव जयते

File No: RJ/26/SEAC2(06)/MIN/EC/1317

State Environment Impact Assessment Authority (SEIAA), Rajasthan

(Constituted as per the provision of EIA Notification, 2006, as amended by the Ministry of Environment, Forest and Climate Change, Government of India)

Dated **10/10/2026**

To,

M/s STAR CEMENT NORTH EAST LIMITED
Mayur Garden, 2nd Floor, Opposite Rajiv Bhawan, G.S. Road, Guwahati, Kamrup As, 781005, In , KAMRUP, ASSAM, , 781005
starcementnel@gmail.com

Subject: **Grant Approval of EIA-EMP and Conditional Environment Clearance Subject to the decision of Hon'ble Supreme Court in Suo Moto Writ Petition (Civil) No. (s) 10/2025 in RE: Definition OF Aravali Hills And Ancillary Issues** for Proposed Proposed "Nimbol Limestone Mine, Block- NB 04", for capacity of 12,00,000 Tones/Year Limestone production and 8,77,665 Tones/Year waste (including inter burden, over burden and soil) with total Excavation: 20,77,665 Tones/Year, in the Mining Lease Area of 33.9047 Ha. at Village(s) - Bogasani, Sinla, Nimbol, Tehsil - Jaitaran, District – Beawar (Rajasthan) by Star Cement North East Limited. **(Proposal no. - 589854)** under the provisions of EIA Notification 2006- regarding.

Sir/Madam,

TThis has reference to your application submitted to SEIAA vide proposal **SIA/RJ/MIN/589854/2026** dated 22/08/2026 of grant of Environmental Clearance (EC) to the aforementioned project under the provision of EIA Notification 2006-and as amended thereof. The proposal has been appraised as per prescribed procedure in the light of provisions under the EIA Notification 2006 on the basis of the mandatory documents enclosed with the application viz. the questionnaire, EIA, EMP and additional clarifications furnished in response to the observation of the State Level Expert Appraisal Committee Rajasthan, in its **6B.270th** meeting held on **07th September, 2026**

2. The particulars of the proposal are as below :

(i) EC Identification No.	EC26B0000RJ5328790N
(ii) File No.	RJ/26/SEAC2(06)/MIN/EC/1317
(iii) Clearance Type	Fresh EC

(iv) Category	B1
(v) Project/Activity Included Schedule No.	1(a) Mining of minerals
(vii) Name of Project	Proposed "Nimbol Limestone Mine, Block- NB 04", for capacity of 12,00,000 Tones/Year Limestone production and 8,77,665 Tones/Year waste (including inter burden, over burden and soil) with total Excavation: 20,77,665 Tones/Year, in the Mining Lease Area of 33.9047 Ha. at Village(s) - Bogasani, Sinla, Nimbol, Tehsil - Jaitaran, District – Beawar (Rajasthan) by Star Cement North East Limited.
(viii) Location of Project (District, State)	Beawar, RAJASTHAN
(ix) Issuing Authority	SEIAA
(x) Applicability of General Conditions	No

2. Brief details of the Project:

1	Category / Item no. (in Schedule):	B1, 1(a) mining of minerals
2	Location of Project	Bogasani, Sinla, Nimbol, Tehsil - Jaitaran, District – Beawar Rajasthan.
3	Project Details M.L.No. /Area/Production capacity/Khasra No.	Area: 33.9047 Ha. Proposed Production capacity of 12,00,000 Tones/Year Limestone production and 8,77,665 Tones/Year waste (including inter burden, over burden and soil) with total Excavation: 20,77,665 Tones/Year
4	Project Cost	Rs. 35.0 Crores
5	Water Requirement & Source	Total water requirement in the mine working will be about 9.5 KLD as below: Dust Suppression -3.5 KLD Plantation -3.0 KLD Drinking & Domestic Requirement-3.0 KLD Source: Ground water and NOC of CGWA obtained
6	Fuel & Energy	Approximately 3.4 KL/day of diesel will be required. The total power requirement for the proposed mine is 80 kVA which will be sourced from Rajasthan State Electricity Board. One portable D.G. set of capacity 100 kVA is also proposed for the power backup.
7	Application No.& Date & documents submitted	Online Proposal No. SIA/RJ/MIN/589854/2026 dated 22/08/2026. Documents: Final EIA/EMP Report along with approved mining plan & all requisite documents for grant of EC have been submitted.
8	Information about Aravalli Certificate	Aravalli Certificate issued by the Assistant Mining Engineer, Jaitaran. vide letter no. Vide Letter No.: Ref. No.: AME/Jaitaran/Map./Aravlli/NB06/376 dated 18.12.2025 stated That mine lease area does not fall within the Aravalli Range and Hills. However it is falling in Aravali polygon as per FSI report dated 25.08.2010
9	Date of Air/Water/Noise Monitoring	Baseline study period Pre-Monsoon Season (March' 2025 to May' 2025)

10	Information about 500 meters composite map & Cluster Certificate	As limestone for cement manufacturing is a major mineral, the cluster provisions applicable to minor minerals only and do not apply on major mineral, therefore Cluster Certificate is not required for the present mining project.

12 Environment Management Plan Rs. 138.56 Lakh (Capital Cost) & Rs. 28.12 Lakh (Recurring Cost)

S. No	Particulars		CapitalCost (Rs. InLacs)	RecurringCost (Rs.InLacs)
1.	EnvironmentalMonitoring(Air,Water,Noise etc.)		_	3
2.	Air Pollution Control	WetDrilling,WaterSprinkler,Dust Suppression	_	2
		Bagfiltersatcrushers(1600TPH Crusher)	25	5
3.	WaterPollutionControl(InstallationofRO Units forHigh-TDSWaterTreatment)		1	0.20
4.	NoisePollutionControl(Acousticenclosures, silences,mufflersetc.)		0.5	0.1
5.	GreenBelt(phasewisegreenbeltdevelopment duringplantationplanperiod)		44.76	11.19
6.	Re-grassingafterceasingminingoperations		23.52	5.88
7.	OccupationalHealth&Safety(Initial& PeriodicalMedicalCheck-Ups)		1.5	0.5
8.	EnvironmentalAwarenessProgram(Vocational Training, SHG's etc.)		_	0.25
9.	ConservationPlanforwildlifeandSchedule– I Species		30.28	-
10.	ActionPlanandYear-wiseBudgetAllocationfor AddressingPublicConsultation.		12.00	-
Total			**138.56**	**28.12**

Corporate Environmental Responsibility (CER)-

1. NameoftheProject&Location:NimbolLimestoneMine,Block-NB04&Villages: Bogasani, Nimbol & Sinla, Tehsil Jaitaran, District Beawar, Rajasthan.
2. TotalProjectCost(Rs):33.0Crores
3. TotalestimatedCERbudget(Rs):12.0Lakh

Sr. No.	CER Activity	Location/Village	Environmental/Public Concern Addressed	Physical Target	EstimatedCostinLakh (Rs)	Timeline for Implementation	ImplementingAgency
1.	Skill developme	Villages-Bogasani,	Skill development	Skill development	2.85	3	SCNEL

	ntandself-employment	Sinla, and Nimbol.	and self-employment	and self-employment training programs for localyouthand women, including tailoring, knitting,beauty parlourtraining, andotherneed-based vocational courses.			
2.	Women Empowerment	Villages-Nimbol, Bogasani, and Sinla Villages.	Support for Women EmpowermentandSelf-Employment	Distributionof Sewing Machines to eligiblewomen.	3.0	3	SCNEL
3.	Tree Plantation &Greenbelt Development	Villages - Bogasani, Nimbol, Kanawas, Ramawas Kalan,and Bikarlai.	Tree Plantation &Greenbelt Development	Treeplantation driveswillbe carriedout.	3.86	3	SCNEL
4.	Public welfare	Villages-Bogasani, Sinla, and Nimbol villages.	Social development ,andpublic welfare	Medical Camp andAwareness Camp	2.29	3	SCNEL
Total					12.0		

SCNEL: Star Cement North East Limited.

Green Belt/ Plantation

GREENBELT DEVELOPMENT PLAN							
Year	**Inside the Lease Area - 7.5m statutory safety (Safety zone)**		**Outside Lease Area**		**Plantation Cost**	**Name of Species**	**Place of Plantation**
	Area (Ha.)	**No. of Trees**	**Area (Ha.)**	**No. of Trees**	As per SEIAA Order No. 2630 dated 10.08.2026, plantation has been proposed at a cost of 5,595 saplings × Rs. 800 = Rs. 44.76 Lakh.	Neem, Arjun, Karanj, Shisham, Jamun, Gular, Ashok and Amaltash etc.	(i)Plantation will be done along the 7.5 m peripheral boundary, where about 853 saplings will be planted. (ii)The remaining plantation of about 4,742 saplings will be
Existing	--	--	--	--			
I	1.7047	853	9.4838	4,742			
II	--	--	--	--			
III	--	--	--	--			
IV	--	--	--	--			
V	--	--	--	--			
Total	**1.7047**	**853**	**9.4838**	**4,742**			
Total No. of Saplings = 11.1885 ha (33% of the total mine lease area)× 500 saplings/ha = 5,595 saplings.					**Total = 44.76 Lakh**		

				done in Nimbol Village, at Khasra No. 1244/316. This land is grazzing land (Gochar) for which NOC has been obtained from Gram Panchayat, Nimbol, for plantation. (iii) Plantation will also be carried out in the backfilled areas, and re-grassing will be undertaken after cessation of mining operations to restore the ecology and rehabilitate the area.
	Budgetary Breakup for Labour A capital cost of 1.5 lakh and a recurring cost of 0.5 lakh per annum have been allocated for Occupational Health & Safety measures, including initial and periodic medical check-ups of workers.			
16	Present Status	This is a Proposed Nimbol Limestone Mine Block - NB 04" for capacity of 12,00,000 Tonnes/Year Limestone production and 8,77,665 Tonnes/Year waste (including inter burden, over burden and soil) with total Excavation: 20,77,665 Tonnes/Year within the mine lease area of 33.9047 hectares coming up at village (s) Bogasani, Sinla, Nimbol, Tehsil - Jaitaran, District – Beawar (Rajasthan)by Star Cement North East LimitedAs per EIA Notification dated 14.09.2006, as amended from time to time this mining project comes under 'B1' Category.		
17	CTE Fees	1,42,000/- submitted on 02.01.2026		

3. In view of the particulars above, the project proposal interalia including Form-2(Part A, B and C)/ EIA & EMP Reports were submitted to the SEIAA for an appraisal by the SEIAA under the provision of EIA notification 2006 and its subsequent amendments.

4. The above-mentioned proposal has been considered by SEIAA in the **meeting 6.229th held on 23/09/2026.** The minutes of the meeting and all the project documents are available on PARIVESH portal which can be accessed from the PARIVESH portal by scanning the QR Code above. Brief description of the project is as under: Limestone will be supplied to the cement plant or sold in the open market to meet industrial demand.

5. Details of the minerals to be mined along with production capacity and the brief on the salient features of the project as submitted by the project proponent in Form 1 (Part A and B) in the reports and as presented during SEIAA are annexed to this EC as Annexure (1).

6. The SEIAA, in its **meeting 6.229th held on 23/09/2026**, based on information submitted viz: Form 1 (Part A, B

and C), EIA/EMP report etc & clarifications provided by the project proponent and after detailed deliberations on all technical aspects and public hearing issues and compliance thereto furnished by the Project Proponent, recommended the proposal for grant of Environment Clearance under the provision of EIA Notification, 2006 and as amended thereof subject to stipulation of Specific and Standard EC conditions as detailed in the point below.

7. **The SEIAA has examined the proposal in accordance with the provisions contained in the Environment Impact Assessment (EIA) Notification, 2006 & further amendments thereto and based on the recommendations of the SEIAA hereby accords Environment Clearance for the instant proposal to M/s. STAR CEMENT NORTH EAST LIMITED under the provisions of EIA Notification, 2006 and as amended thereof subject to compliance of the Specific and Standard EC conditions as given in Annexure (1)**

8. **Aravali Condition:**
   I. This Conditional Environmental Clearance is strictly conceptual and regulatory. It does not constitute a final permission to mine under the orders of the Hon'ble Supreme Court dated 09.05.2024, 29.12.2025, and 26.02.2026. The project proponent is completely prohibited from clearing land, setting up machinery, or executing any physical intervention at the site until an explicit, project-specific permission is secured directly from the Hon'ble Supreme Court of India.
   II. The Conditional Environmental Clearance is based on current geographic coordinates, and if the upcoming Supreme Court-constituted Committee redefines or alters the boundaries/extents of the Aravalli polygon, and mining activity is prohibited by the Hon'ble Supreme Court at that time, then this EC shall automatically stand revoked, and the Project Proponent will have to seek a fresh appraisal from SEIAA.

   III. It is re-iterated that this EC is being granted but it shall remain subject to the orders dated 09.05.2024, 29.12.2025 & 26.02.2026 and all further orders/ judgements pronounced by Hon'ble Supreme Court in the matter of Suo Moto Writ Petition (Civil) No. (s) 10/2025 and it shall be the sole duty and responsibility of the PP to ensure full compliance of all orders issued in this case and/ or any other related I.As/ Matters.

9. The SEIAA reserves the right to stipulate additional conditions, if found necessary.

10. The Environmental Clearance to the aforementioned project is under provisions of EIA Notification, 2006. It does not tantamount to approvals/consent/permissions etc. required to be obtained under any other Act/Rule/regulation. The Project Proponent is under obligation to obtain approvals /clearances under any other Acts/ Regulations or Statutes, as applicable, to the project.

11. The PP is under obligation to implement commitments made in the Environment Management Plan, which forms part of this EC.

12. Validity of EC will be in accordance with the MOEF &CC , OM dated 13/12/2022 & its Clarifications issued time to time .

13. **General Instructions:**

    1. The project proponent shall prominently advertise it at least in two local newspapers of the District or State, of which one shall be in the vernacular language within seven days indicating that the project has been accorded environment clearance and the details of SEIAA website where it is displayed.

    2. The copies of the environmental clearance shall be submitted by the project proponents to the Heads of local bodies, Panchayats and Municipal Bodies in addition to the relevant offices of the Government who in turn must display the same for 30 days from the date of receipt.

    3. The project proponent shall have a well laid down environmental policy duly approved by the Board of Directors (in case of Company) or competent authority, duly prescribing standard operating procedures to have proper checks and balances and to bring into focus any infringements/deviation/violation of the environmental / forest / wildlife norms / conditions.

    4. Action plan for implementing EMP and environmental conditions along with responsibility matrix of the project proponent (during construction phase) and authorized entity mandated with compliance of conditions (during operational phase) shall be prepared. The year wise funds earmarked for environmental

protection measures shall be kept in separate account and not to be diverted for any other purpose. Six monthly progress of implementation of action plan shall be reported to the Ministry/Regional Office along with the Six-Monthly Compliance Report.

5. Concealing factual data or submission of false/fabricated data may result in revocation of this environmental clearance and attract action under the provisions of Environment (Protection) Act, 1986.
6. The Regional Office of this SEIAAshall monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the officer (s) of the Regional Office by furnishing the requisite data / information/monitoring reports.
7. Any appeal against this EC shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

14. This issue with an approval of the Competent Authority.

(Shailaja Deval)
Member Secretary,
SEIAA, Rajasthan

Copy To

1. The Additional Chief Secretary, Environment Department Rajasthan, Secretariat Jaipur Rajasthan, Jaipur, Rajasthan, env.dept@rajasthan.gov.in
2. The Chairman, SEIAA, Room No. 101 Aravalli Bhawan Jhalana Institutional Area Jaipur Rajasthan, Jaipur, Rajasthan, gargmunish40@gmail.com
3. The Member, SEIAA, Room No. 103 Aravalli Bhawan Jhalana Institutional Area Jaipur Rajasthan, Jaipur, Rajasthan, jhajhariamanphool@gmail.com
4. The Deputy Director General, Regional Office, Inspector General Of Forests (Central) Sub-Office Jaipur Ministry Of Environment Forest And Climate Change Sub-Office Jaipur A-209 And 218 Aranya Bhawan Mahatma Gandhi Road Jhalana Institutional Area Jaipur – 304002 Rajasthan., N/A, N/A, iro.jaipur-mefcc@gov.in
5. The Member Secretary, SPCB/PCC, 4 Institutional Area Jhalana Doongri, Jaipur, Rajasthan, member-secretary@rpcb.nic.in
6. The Member Secretary, State Level Expert Appraisal Committee (SEAC-2), Rspcb Office Jhalana Institutional Areajaipurrajasthan, Jaipur, Rajasthan, rajseac2six@gmail.com
7. The The Director, Department of Mine & Geology, Court Chorha Udaipur Udaipur Rajasthan, Jaipur, Rajasthan, director.uda.mg@rajasthan.gov.in

Annexure 1

Standard EC Conditions for (Mining of minerals)

1. Statutory Compliance

S. No	EC Conditions
1.1	The Project proponent complies with all the statutory requirements and judgment of Hon'ble Supreme Court dated 2nd August, 2017 in Writ Petition (Civil) No. 114 of 2014 in matter of Common Cause versus Union of India &Ors before commencing the mining operations.
1.2	The Project Authorities should widely advertise about the grant of this EC letter by printing the same in at least two local newspapers, one of which shall be in vernacular language of the concerned area. The advertisement shall be done within 7 days of the issue of the clearance letter

S. No	EC Conditions
	mentioning that the instant project has been accorded EC and copy of the EC letter is available with the State Pollution Control Board/Committee and web site of the Ministry of Environment, Forest and Climate Change (www.parivesh.nic.in). A copy of the advertisement may be forwarded to the concerned MoEFCC Regional Office for compliance and record.
1.3	This Environmental Clearance (EC) is subject to orders/ judgment of Honble Supreme Court of India, Honble High Court, Honble NGT and any other Court of Law, Common Cause Conditions as may be applicable.
1.4	State Pollution Control Board/Committee shall be responsible for display of this EC letter at its Regional office, District Industries Centre and Collector's office/ Tehsildar's Office for 30 days.
1.5	A copy of EC letter will be marked to concerned Panchayat / local NGO etc. if any, from whom suggestion / representation has been received while processing the proposal.
1.6	The Project Proponent shall follow the mitigation measures provided in MoEFCC's Office Memorandum No. Z-11013/57/2014-IA.II (M), dated 29th October, 2014, titled "Impact of mining activities on Habitations-Issues related to the mining Projects wherein Habitations and villages are the part of mine lease areas or Habitations and villages are surrounded by the mine lease area."
1.7	The State Government concerned shall ensure that mining operation shall not be commenced till the entire compensation levied, if any, for illegal mining paid by the Project Proponent through their respective Department of Mining & Geology in strict compliance of Judgment of Hon'ble Supreme Court dated 2nd August, 2017 in Writ Petition (Civil) No. 114 of 2014 in matter of Common Cause versus Union of India & Ors.
1.8	The Project Proponent shall inform the MoEF&CC for any change in ownership of the mining lease. In case there is any change in ownership or mining lease is transferred. PP needs to apply for transfer of EC as per provisions of the para 11 of EIA Notification, 2006 as amended from time to time.

2. Air Quality Monitoring And Preservation

S. No	EC Conditions
2.1	Effective safeguard measures for prevention of dust generation and subsequent suppression (like regular water sprinkling, metalled road construction etc.) shall be carried out in areas prone to air pollution wherein high levels of PM10 and PM2.5 are evident such as haul road, loading and unloading point and transfer points. The Fugitive dust emissions from all sources shall be regularly controlled by installation of required equipments/ machineries and preventive maintenance. Use of suitable water-soluble chemical dust suppressing agents may be explored for better effectiveness of dust control system. It shall be ensured that air pollution level conform to the standards prescribed by the MoEFCC/ Central Pollution Control Board.
2.2	The Project Proponent shall Carry out Ambient Air Quality Monitoring periodically from the State Board or CPCB Approved Laboratory, 1 (one) in upwind and 2 (two) in downwind direction based on long term climatological data about wind direction such that an angle of 120° is made between the monitoring locations to monitor critical parameters, relevant for mining operations, of air pollution viz. PM10, PM2.5, NO2, CO and SO2 etc. as per the methodology mentioned in NAAQS Notification No. B-29016/20/90/PCI/I, dated 18.11.2009 covering the aspects of transportation and

S. No	EC Conditions
	use of heavy machinery in the impact zone. The ambient air quality shall also be monitored at prominent places like office building, canteen etc. as per the site condition to ascertain the exposure characteristics at specific places.

3. Water Quality Monitoring And Preservation

S. No	EC Conditions
3.1	Quality of polluted water generated from mining operations which include Chemical Oxygen Demand (COD) in mines run-off; acid mine drainage and metal contamination in runoff shall be monitored along with Total Suspended Solids (TDS), Dissolved Oxygen (DO), pH and Total Suspended Solids (TSS). The monitored data shall be uploaded on the website of the company as well as displayed at the project site in public domain, on a display board, at a suitable location near the main gate of the Company. The circular No. J- 20012/1/2006-IA.II (M) dated 27.05.2009 issued by Ministry of Environment, Forest and Climate Change may also be referred in this regard.
3.2	Project Proponent shall plan, develop and implement rainwater harvesting measures on long term basis to augment ground water resources in the area in consultation with Central Ground Water Board/ State Groundwater Department. A report on amount of water recharged needs to be submitted to Regional Office MoEFCC annually.
3.3	Industrial waste water (workshop and waste water from the mine) should be properly collected and treated so as to conform to the notified standards prescribed from time to time. The standards shall be prescribed through Consent to Operate (CTO) issued by concerned State Pollution Control Board (SPCB). The workshop effluent shall be treated after its initial passage through Oil and grease trap.
3.4	The water balance/water auditing shall be carried out and measure for reducing the consumption of water shall be taken up and reported to the Regional Office of the MoEF&CC and State Pollution Control Board/Committee.
3.5	In case, immediate mining scheme envisages intersection of ground water table, then Environmental Clearance shall become operational only after receiving formal clearance from CGWA. In case, mining operation involves intersection of ground water table at a later stage, then PP shall ensure that prior approval from CGWA and MoEFCC is in place before such mining operations. The permission for intersection of ground water table shall essentially be based on detailed hydro-geological study of the area.
3.6	The Project Proponent shall undertake regular monitoring of natural water course/ water resources/ springs and perennial nallahs existing/ flowing in and around the mine lease including upstream and downstream. Sufficient number of gullies shall be provided at appropriate places within the lease for management of water. The parameters to be monitored shall include their water quality vis-à-vis suitability for usage as per CPCB criteria and flow rate. It shall be ensured that no obstruction and/ or alteration be made to water bodies during mining operations without justification and prior approval of MoEFCC. The monitoring of water courses/ bodies existing in lease area shall be carried out four times in a year viz. pre- monsoon (April May), monsoon (August), post-monsoon (November) and winter (January) and the record of monitored data may be sent regularly to Ministry of Environment, Forest and Climate Change and its Regional Office, Central Ground Water Authority and Regional Director, Central Ground Water Board, State Pollution Control Board and Central Pollution Control Board. Clearly showing the trend analysis on six-monthly basis.

S. No	EC Conditions
3.7	Project Proponent shall regularly monitor and maintain records w.r.t. ground water level and quality in and around the mine lease by establishing a network of existing wells as well as new piezo-meter installations during the mining operation in consultation with Central Ground Water Authority/ State Ground Water Department. The Report on changes in Ground water level and quality shall be submitted on six-monthly basis to the Regional Office of the Ministry, CGWA and State Groundwater Department / State Pollution Control Board.

4. Noise And Vibration Monitoring And Prevention

S. No	EC Conditions
4.1	The Project Proponent shall take measures for control of noise levels below 85 dBA in the work environment. The workers engaged in operations of HEMM, etc. should be provided with ear plugs /muffs. All personnel including laborers working in dusty areas shall be provided with protective respiratory devices along with adequate training, awareness and information on safety and health aspects. The PP shall be held responsible in case it has been found that workers/ personals/ laborers are working without personal protective equipment.
4.2	The illumination and sound at night at project sites disturb the villages in respect of both human and animal population. Consequent sleeping disorders and stress may affect the health in the villages located close to mining operations. Habitations have a right for darkness and minimal noise levels at night. PPs must ensure that the biological clock of the villages is not disturbed; by orienting the floodlights/ masks away from the villagers and keeping the noise levels well within the prescribed limits for day /night hours.
4.3	The peak particle velocity at 500m distance or within the nearest habitation, whichever is closer shall be monitored periodically as per applicable DGMS guidelines.

5. Mining Plan

S. No	EC Conditions
5.1	The Project Proponent shall adhere to approved mining plan, inter alia, including, total excavation (quantum of mineral, waste, over burden, inter burden and top soil etc.); mining technology; lease area; scope of working (method of mining, overburden & dump management, O.B& dump mining, mineral transportation mode, ultimate depth of mining, concurrent reclamation and reclamation at mine closure; land-use of the mine lease area at various stages of mining scheme as well as at the end-of-life; etc.).
5.2	The land-use of the mine lease area at various stages of mining scheme as well as at the end-of-life shall be governed as per the approved Mining Plan. The excavation vis-à-vis backfilling in the mine lease area and corresponding afforestation to be raised in the reclaimed area shall be governed as per approved mining plan. PP shall ensure the monitoring and management of rehabilitated areas until the vegetation becomes self-sustaining. The compliance status shall be submitted half-yearly to the MoEFCC and its concerned Regional Office.

6. Land Reclamation

S. No	EC Conditions
6.1	Check dams of appropriate size, gradient and length shall be constructed around mine pit and OB dumps to prevent storm run-off and sediment flow into adjoining water bodies. A safety margin of 50% shall be kept for designing of sump structures over and above peak rainfall (based on 50 years data) and maximum discharge in the mine and its adjoining area which shall also help in providing adequate retention time period thereby allowing proper settling of sediments/ silt material. The sedimentation pits/ sumps shall be constructed at the corners of the garland drains.
6.2	The Overburden (O.B.), waste and topsoil generated during the mining operations shall be stacked at earmarked OB dump site(s) only and it should not be kept active for a long period of time. The physical parameters of the OB / waste dumps / topsoil dump like height, width and angle of slope shall be governed as per the approved Mining Plan and the guidelines/circulars issued by D.G.M.S. The topsoil shall be used for land reclamation and plantation.
6.3	Catch drains, settling tanks and siltation ponds of appropriate size shall be constructed around the mine working, mineral yards and Top Soil/OB/Waste dumps to prevent run off of water and flow of sediments directly into the water bodies (Nallah/ River/ Pond etc.). The collected water should be utilized for watering the mine area, roads, green belt development, plantation etc. The drains/ sedimentation sumps etc. shall be de-silted regularly, particularly after monsoon season, and maintained properly.
6.4	The slope of dumps shall be vegetated in scientific manner with suitable native species to maintain the slope stability, prevent erosion and surface run off. The selection of local species regulates local climatic parameters and help in adaptation of plant species to the microclimate. The gullies formed on slopes should be adequately taken care of as it impacts the overall stability of dumps. The dump mass should be consolidated with the help of dozer/ compactors thereby ensuring proper filling/ leveling of dump mass. In critical areas, use of geo textiles/ geo-membranes / clay liners / Bentonite etc. shall be undertaken for stabilization of the dump.
6.5	The Project Proponent shall make necessary alternative arrangements for livestock feed by developing grazing land with a view to compensate those areas which are coming within the mine lease. The development of such grazing land shall be done in consultation with the State Government. In this regard, Project Proponent should essentially implement the directions of the Hon'ble Supreme Court with regard to acquisition of grazing land. The sparse trees on such grazing ground, which provide mid-day shelter from the scorching sun, should be scrupulously guarded/ protected against felling and plantation of such trees should be promoted.

7. Transportation

S. No	EC Conditions
7.1	No Transportation of the minerals shall be allowed in case of roads passing through villages/ habitations. In such cases, PP shall construct a 'bypass' road for the purpose of transportation of the minerals leaving an adequate gap (say at least 200 meters) so that the adverse impact of sound and dust along with chances of accidents could be mitigated. All costs resulting from widening and strengthening of existing public road network shall be borne by the PP in consultation with nodal State Govt. Department. Transportation of minerals through road movement in case of existing village/ rural roads shall be allowed in consultation with nodal State Govt. Department only after required strengthening such that the carrying capacity of roads is increased to handle the traffic load. The pollution due to transportation load on the environment will be effectively controlled and

S. No	EC Conditions
	water sprinkling will also be done regularly. Vehicular emissions shall be kept under control and regularly monitored. Project should obtain Pollution Under Control (PUC) certificate for all the vehicles from authorized pollution testing centers. [If applicable in case of road transport].
7.2	The Main haulage road within the mine lease should be provided with a permanent water sprinkling arrangement for dust suppression. Other roads within the mine lease should be wetted regularly with tanker-mounted water sprinkling system. The other areas of dust generation like crushing zone, material transfer points, material yards etc. should invariably be provided with dust suppression arrangements. The air pollution control equipments like bag filters, vacuum suction hoods, dry fogging system etc. shall be installed at Crushers, belt-conveyors and other areas prone to air pollution. The belt conveyor should be fully covered to avoid generation of dust while transportation. PP shall take necessary measures to avoid generation of fugitive dust emissions.

8. Green Belt

S. No	EC Conditions
8.1	The Project Proponent shall develop greenbelt in 7.5m wide safety zone all along the mine lease boundary as per the guidelines of CPCB in order to arrest pollution emanating from mining operations within the lease. The whole Green belt shall be developed within first 5 years starting from windward side of the active mining area. The development of greenbelt shall be governed as per the EC granted by the Ministry irrespective of the stipulation made in approved mine plan.
8.2	The Project Proponent shall carryout plantation/ afforestation in backfilled and reclaimed area of mining lease, around water body, along the roadsides, in community areas etc. by planting the native species in consultation with the State Forest Department/ Agriculture Department/ Rural development department/ Tribal Welfare Department/ Gram Panchayat such that only those species be selected which are of use to the local people. The CPCB guidelines in this respect shall also be adhered. The density of the trees should be around 2500 saplings per Hectare. Adequate budgetary provision shall be made for protection and care of trees.

9. Public Hearing And Human Health Issues

S. No	EC Conditions
9.1	Project Proponent shall make provision for the housing for workers/labors or shall construct labor camps within/outside (company owned land) with necessary basic infrastructure/ facilities like fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche for kids etc. The housing may be provided in the form of temporary structures which can be removed after the completion of the project related infrastructure. The domestic waste water should be treated with STP in order to avoid contamination of underground water.

10. Corporate Environment Responsibility

S. No	EC Conditions
10.1	The Project Proponent shall submit the time- bound action plan to the concerned regional office of the Ministry within 6 months from the date of issuance of environmental clearance for undertaking

S. No	EC Conditions
	the activities committed during public consultation by the project proponent and as discussed by the EAC, in terms of the provisions of the MoEF&CC Office Memorandum No.22-65/2017-IA.III dated 30 September, 2020. The action plan shall be implemented within three years of commencement of the project.

11. Miscellaneous

S. No	EC Conditions
11.1	The concerned Regional Office of the MoEF&CC shall randomly monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the MoEF&CC officer(s) by furnishing the requisite data / information / monitoring reports.
11.2	A separate 'Environmental Management Cell' with suitable qualified manpower should be set-up under the control of a Senior Executive. The Senior Executive shall directly report to Head of the Organization. Adequate number of qualified Environmental Scientists and Mining Engineers shall be appointed and submit a report to RO, MoEF&CC.
11.3	Concealing factual data failure to comply with any or submission of false/ fabricated data and of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of Environment (Protection) Act, 1986.
11.4	In pursuant to Ministrys O.M No 22-34/2018-IA.III dated 16.01.2020 to comply with the direction made by Honble Supreme Court on 8.01.2020 in W.P. (Civil) No 114/2014 in the matter Common Cause vs Union of India, the mining lease holder shall after ceasing mining operations, undertake regrassing the mining area and any other area which may have been disturbed due to other mining activities and restore the land to a condition which is fit for growth of fodder, flora, fauna etc.
11.5	Any appeal against this environmental clearance shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.
11.6	The Project Proponent shall prepare digital map (land use & land cover) of the entire lease area once in five years purpose of monitoring land use pattern and submit a report to concerned Regional Office of the MoEF&CC.
11.7	The above conditions will be enforced inter-alia, under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and the Public Liability Insurance Act, 1991 along with their amendments and rules made there under and also any other orders passed by the Hon'ble Supreme Court of India/High Court and any other Court of Law relating to the subject matter.
11.8	The Ministry or any other competent authority may alter/modify the above conditions or stipulate any further condition in the interest of environment protection.
11.9	The Project Proponent shall submit six monthly compliance reports on the status of the implementation of the stipulated environmental safeguards to the MOEFCC & its concerned Regional Office, Central Pollution Control Board and State Pollution Control Board.

S. No	EC Conditions
11.10	The Project Authorities should inform to the Regional Office regarding date of financial closures and final approval of the project by the concerned authorities and the date of start of land development work.

Additional EC Conditions

The Authority decided to impose the following Additional Condition:

1. Aravali Condition:

I. This Conditional Environmental Clearance is strictly conceptual and regulatory. It does not constitute a final permission to mine under the orders of the Hon'ble Supreme Court dated 09.05.2024, 29.12.2025, and 26.02.2026. The project proponent is completely prohibited from clearing land, setting up machinery, or executing any physical intervention at the site until an explicit, project-specific permission is secured directly from the Hon'ble Supreme Court of India.

II. The Conditional Environmental Clearance is based on current geographic coordinates, and if the upcoming Supreme Court-constituted Committee redefines or alters the boundaries/extents of the Aravalli polygon, and mining activity is prohibited by the Hon'ble Supreme Court at that time, then this EC shall automatically stand revoked, and the Project Proponent will have to seek a fresh appraisal from SEIAA.

III. It is re-iterated that this EC is being granted but it shall remain subject to the orders dated 09.05.2024, 29.12.2025 & 26.02.2026 and all further orders/ judgements pronounced by Hon'ble Supreme Court in the matter of Suo Moto Writ Petition (Civil) No. (s) 10/2025 and it shall be the sole duty and responsibility of the PP to ensure full compliance of all orders issued in this case and/ or any other related I.As/ Matters.

2. That the PP shall apply and obtain Consent to Operate under Water Act/Air Act for total excavation i.e Proposed Production Capacity: 20,77,665TPA (ROM) [Lime Stone12,00,000 TPA + Waste 8,77,665 TPA] for which EC is granted.

3. The PP shall ensure compliance of Ministry's OM dated 29.10.2014 issued for mining projects wherein habitations and villages are the part of mine lease areas or habitations and villages are surrounded by the mine lease area

Beside this proponent shall also comply the following condition forward by RSPCB to SEIAA for CTE in compliance of MOEF&CC Dated 08.10.2025:-

1. That all the PCM needed to mitigate the fugitive emission shall be strictly followed. It includes water sprinkling etc. The Trucks or other transportation medium involved shall be covered with tarpaulin.
2. That ground water shall not be abstracted or ground water table shall not be intersected without prior permission of the Central Ground Water Authority (CGWA).
3. That internal transport roads (Haul roads) should be Paved/Hard Surfaced using bitumen etc and compliance shall be submitted with photographic evidence by 3 months.
4. That adequate measure shall be taken for control of fugitive emissions from the areas prone to air pollution.
5. That you shall not operate any stone crusher/mineral grinding/mineral processing plant within said lease without obtaining prior consent of the State Board.
6. That this consent to establish shall not be valid, if the lessee has not obtained permissions required, if any, from NBWL/Forest Department etc. with respect to Wild Life Sanctuary /National Parks/ Critical Tiger Habitats in compliance of various orders passed by any other law/act/rule/ regulation

or order of MoEF&CC and/or any Court/Tribunal time to time.

7. That regular water sprinkling should be carried out in critical areas prone to air pollution and having high levels of SPM and RSPM such as on haul road, loading and unloading points and transfer points.
8. That the mine shall install adequately design rain water harvesting structure for prevention and recharge of ground water in and around the lease area.
9. That the mine shall not allow making any obstacles to any natural water flow i.e., natural nallah/steam carrying rain water to any water body.
10. This the mine shall not allow unauthorized disposal of any solid waste on land inside or outside the premises.
11. That this consent to establish shall be subject to compliance of direction/order passed by Courts of Law in the matter, if any.
12. That the lessee should dump the overburden in such a manner that it does not get washed away to nearby water tanks and lakes etc. during rainy season.
13. That this consent shall be subject to validity of mining lease.

Member Secretary
SEIAA, (Rajasthan)

Signature Not Verified

Digitally Signed by : Smt Shailaja Deval
Member Secretary, SEIAA

Date: 10/10/2026